

# Matteson Connection #3



## PROJECT OVERVIEW

**Project:**  
*Matteson Connection #3*  
*Matteson, IL*

**Client:**  
*CN Railway Southern Region*  
*Elgin, Joliet & Eastern Railway Company*

**Contract:**  
*General Contractor*



**Harbour Contractors, Inc.** cut and filled approximately 187,000 CY to provide the proper topography for installation of the southeast connection, loop connection and northeast connection between the IC main lines and the EJ&E main lines.

Included in this area of the new track is a triple crossing across Main Street. This project included removal and replacement of an approximately ¼ mile stretch of road including medians, curb and gutter, underground structures, and pavement. We furnished and installed approximately 14,000 track feet of new rail (of both wood tie-continuous welded rail and concrete tie-continuous welded rail), realigned approximately 2,600 track feet of existing rail, and removed approximately 20,000 track feet of existing rail. We also installed twelve new switches and installed sewer structures and culverts to manage the water over the site.